HZS240 Concrete Batching Plant

240 m³/h stationary batching plant · Major ready-mix operations and the largest infrastructure pours

Parameter	Value
Model	HZS240
Theoretical productivity	240 m³/h
Mixer	JS4000 Twin-Shaft
Mixer discharge capacity	4 m³
Discharge height	4.2 m
Aggregate bins	4 × 40 m³
Weighing accuracy	Aggregate ±2%, Cement ±1%, Water ±1%
Total power	~400 kW
Control system	Fully automatic PLC + PC
Certification	CE, ISO 9001

Site requirements: confirm supply voltage and frequency at order — the plant is built to your specification. On grids with frequent outages a standby generator must be sized on motor starting current, not on the 400 kW installed figure. The concrete foundation must be built from the general arrangement drawing for your exact configuration; anchor bolt positions and load data differ between models.

HZS GLOBAL — Concrete Equipment Supply
Email: hzs@hzsglobal.com | WhatsApp: +86 187 6888 8850 | www.hzsglobal.com